

Springville 400 East Roadway Reconstruction

New Road Project / Staker Parson - Contractor

What: Phase One Road Reconstruction

Road Reconstruction of 400 East
From 1500 South to 400 South

Work Includes: Storm Drain, Curb and Gutter,
Some areas of Sidewalk, Modifying sidewalk ramps in
some intersections to make them wheelchair accessible,
reconstructing the road.

When:

Work is scheduled to begin: July 6, 2010

Work Complete: Approximately September 15, 2010

Details:

Access to businesses will be maintained.

There will be occasional temporary restrictions to access
during the reconstruction operation. Alternate routes will
be provided.

Access to residential properties will be maintained.

Work will take place from 7 am until 7 pm Monday—
Friday with occasional work on weekends.

Dust will be controlled seven days a week.

Ramps will be provided as necessary to maintain access to
houses every night.

Road Reconstruction operation consists of:

- 1) Excavating and removing old roadway material to a depth of 24 inches.
- 2) Back filling and compacting with 12 inches of select fill material and 8 inches of structural road base.
- 3) Installation of curb and gutter and individual driveway approaches.
- 4) Roadway surfacing with four inches of new asphalt pavement.

Realities of Construction What to Expect:

Dust

Noise and Vibrations

Traffic Delays

Modified Access to
Properties

Brief Utility Interruptions

Contact information:

For questions or concerns

Phone: 1-800-278-4282

Email:
scott@ja-today.com

If you would like email
updates about the project
email:
scott@ja-today.com

Please put 400 East
in the subject line for all
emails related to this
project.